

**DTEK<sup>®</sup>**

Dansk Teknikentreprise A/S

# VANDTÅGE I BYGNINGER

DBI - Sikkerhedens Hus

Maj 2013

# TORBEN GULDBÆK JENSEN



Projektleder hos DTEK A/S

Uddannet blikkenslager

10 års erfaring som sprinklermontør i “marken”

2 år på kontor som projektleder med hovedvægten på sprinkler

# DTEK- DANSK TEKNIK ENTERPRISE A/S

- Grundlagt i 2001 .
- DTEK A/S beskæftiger omkring 80 montører, med afdelinger i København og Støvring.
- DTEK A/S er akkrediteret og certificeret under DS/EN ISO 9001:2000.
- DTEK A/S vores kerneydelser er VVS og sprinkler
- DTEK I samarbejde med Novenco på flere projekter siden 2007 fra plejehjem til kontorhuse  
Projekter under opførelse:
- Ingeniørfirmaet Moe, nyt domicil, Gladsaxe – 25000m<sup>2</sup>.
- Turbinehallerne, Middelfart 2500 m<sup>2</sup>

The logo consists of the word "DTEK" in a bold, black, sans-serif font, followed by a registered trademark symbol (®). The text is centered within a solid brown square background.

**DTEK<sup>®</sup>**

**Dansk Teknikentreprise A/S**

The logo consists of the word "DTEK" in a bold, black, sans-serif font, followed by a registered trademark symbol (®). The text is centered within a solid brown square background.


**DTEK<sup>®</sup>**

Dansk Teknikentreprise A/S


# SPRINKLER VS. VANDTÅGE SYSTEM

	Conventional Sprinkler System	Water Mist System
<b>Pressure at Nozzle</b>	0.5 bar	4 bar
<b>Way of extinguination</b>	Cooling	Cooling and Oxygen suffocation
<b>System configuration</b>	Difficult	Simple
<b>Price</b>	Low	Low
<b>Water consumption</b>	5 l/min/m <sup>2</sup>	1.6l /min/m <sup>2</sup>
<b>Pipe size</b>	Large	Small
<b>Recommended Pipe material</b>	Steel	Stainless steel, Galvanized pipes
<b>Working Pressure</b>	< 12 bar	<16 bar
<b>Fitting</b>	Sprinklerfitting	Pressfitting
<b>Max. Areal coverage pr. sprinkler</b>	12m <sup>2</sup>	25, 26, 30 m <sup>2</sup>
<b>Installation time</b>	100 %	40 %

# DYSER TIL MONTAGE I LOFT



# DYSER MONTERET I NEDHÆNGT LOFT






# FLEKSIBEL TILSLUTNING



# SPRINKLER MONTERET I NEDHÆNGT LOFT






Sprinkler




# VANDTÅGE SYSTEM


- Simpel pålidelig system
- Tidsbesparende montering
- Større dækningsareal pr. enhed
- Mindre rør dimensioner
- Standard vvs komponenter
- Op til 50% mindre vandmængde-
  - F.ex. 1600l/min traditionel vs. 700l/min Novenco vandtåge system
- Press fitting- lettere vedligeholdelse
- Arkitektonisk tiltalende – concealed sprinkler
- Ergonomisk fordelagtig - mindre nedslidning af medarbejderne grundet den lavere vægt.



# AKTIVERET DYSE



# OVERSIGT VANDTÅGEDYSER




# CLOSED NOZZLE NF18A-CA26

WATER MIST NOZZLE



Lloyds Approved



**TECHNICAL DATA:**

- Nozzle Material: Brass M558/NiSn
- Installation: Pendant installation
- Flow Calculation:  $Q = k\sqrt{\text{Working pressure}}$
- B: Ceiling hole diameter: 35mm-40mm
- C: Nozzle diameter: M32 x 1 - Ø32
- D: Top ring shaft diameter: 40mm
- E: Top ring plate diameter: 50mm
- F: Cover below ceiling: 15mm
- G: Ceiling thickness: 0-18mm
- H: Height of top ring: 18mm
- I: Nozzle stem length: 50mm
- J: 1/2" Pipe thread nipple: 18mm


Type:	NF18A-CA26, 57/68°C	NF 18A-CA26, 141°C
Working Pressure	[bar]	3,4
K-factor	[L / min * bar <sup>1/2</sup> ]	31,3
Max. spacing between nozzles	m * m	4 x 6,5
Density of coverage	[L / min * m <sup>2</sup> ]	2,22

Owing to continued product development, Novenco reserves the right to introduce alterations without prior notice.

[www.novenco-ft.com](http://www.novenco-ft.com)

# CLOSED NOZZLE, NHP-18 A

WATER MIST NOZZLE



**TECHNICAL DATA:**

- Nozzle Material: Brass M558/NiSn
- Installation: Pendant installation
- Flow Calculation:  $Q = k\sqrt{\text{Working pressure}}$
- B: Ceiling hole diameter: 35mm-40mm
- C: Nozzle diameter: M32 x 1 - Ø32
- D: Top ring shaft diameter: 40mm
- E: Top ring plate diameter: 50mm
- F: Cover below ceiling: 15mm
- G: Ceiling thickness: 0-18mm
- H: Height of top ring: 18mm
- I: Nozzle stem length: 50mm
- J: ½" Pipe thread nipple: 18mm

Type:		NHP 18A, 57/68°C	NHP 18A, 93°C	NHP 18A, 141°C
Working Pressure	[bar]	4	4	4
K-factor	[L / min * bar <sup>1/2</sup> ]	20	20	20
Max. spacing between nozzles	m * m	5 x 5	5 x 5	5 x 5
Density of coverage	[L / min * m <sup>2</sup> ]	1,6	1,6	1,6

Owing to continued product development, Novenco reserves the right to introduce alterations without prior notice.

[www.novenco-ff.com](http://www.novenco-ff.com)




# CLOSED NOZZLE NF18 A-OP50

WATER MIST NOZZLE



Lloyds Approved  
OH1 & OH3



## TECHNICAL DATA:

Nozzle Material:	Brass MS58/NiSn
Installation:	Pendant installation
Flow Calculation:	$Q = kv\sqrt{\text{Working pressure}}$
B: Ceiling hole diameter:	35mm-40mm
C: Nozzle diameter:	M32 x 1 - Ø32
D: Top ring shaft diameter:	40mm
E: Top ring plate diameter:	50mm
F: Cover below ceiling:	15mm
G: Ceiling thickness:	0-18mm
H: Height of top ring:	18mm
I: Nozzle stem length:	50mm
J: ½" Pipe thread nipple:	18mm


Type:		NF18A op50, 57/68°C	NF18AOP50, 93°C	NF18Aop50, 141°C
Working Pressure	[bar]	3,4	3,4	3,4
K-factor	[L / min * bar <sup>1/2</sup> ]	31,4	31,4	31,4
Max. spacing between nozzles	m * m	5,5 x 5,5	5,5 x 5,5	5,5 x 5,5
Density of coverage	[L / min * m <sup>2</sup> ]	1,92	1,92	1,92

Owing to continued product development, Novenco reserves the right to introduce alterations without prior notice.


[www.novenco-ff.com](http://www.novenco-ff.com)




# NEM OPMÅLING



# NEM TILDANNELSE AF RØR





# HURTIG MONTAGE



# OMBYGNING AF GAMMEL FABRIK TIL KONTOR 20000 M2 KLASSIFICERET SOM OH2




# ATRIUM







# ATRIUM DYSE OH2







# STUE PLAN MED ATRIUM




Working Pressure [Bar]	Spray Angle [deg]	Max. Length [m]
4	60	4,6
9	60	7,4



Working Pressure [Bar]	Spray Angle [deg]	Max. Length [m]
4	70	4,4
9	70	5,5

# STUE PLAN MED VANDTÅGE GRID SYSTEM MED Ø56 MM FZ RØR



PLAN AF STUEETAGE Stueplan Bygning B

# MED KUN 10 CM HULRUM OVER NEDHÆNGT LOFT



# PROJEKTER UNDER OPFØRELSE



# TURBINEHALLEN, MIDDELFART OMBYGNING TIL KONTORER - 2500 M<sup>2</sup>



# MOE, GLADSAXE NYT DOMICIL 25000 M<sup>2</sup>






# WATER TANK, SPRINKLER VS MIST SYSTEM

Table 9 — Minimum water volume for pre-calculated LH and OH systems

Group	Height $h$ of the highest sprinkler above the lowest sprinkler $(A_1)$ (see NOTE) $(A_1)$ m	Minimum water volume $m^3$
LH - (Wet or pre-action)	$h \leq 15$	9
	$15 < h \leq 30$	10
	$30 < h \leq 45$	11
OH1 - Wet or pre-action	$h \leq 15$	55
	$15 < h \leq 30$	70
	$30 < h \leq 45$	80
OH1 - Dry or alternate OH2 - Wet or pre-action	$h \leq 15$	105
	$15 < h \leq 30$	125
	$30 < h \leq 45$	140
OH2 - Dry or alternate OH3 - Wet or pre-action	$h \leq 15$	135
	$15 < h \leq 30$	160
	$30 < h \leq 45$	185
OH3 - Dry or alternate OH4 - Wet or pre-action	$h \leq 15$	160
	$15 < h \leq 30$	185
	$30 < h \leq 45$	200
OH4 - Dry or alternate	Use HH protection	
$(A_1)$ NOTE $(A_1)$ Excluding sprinklers in the sprinkler valve room.		

Water flow required: 580 l/min		
Duration: 60 min		
Water tank V m <sup>3</sup>		
Water tank V = 580 l/min x 60 min		
Water tank V = 34,8 m <sup>3</sup>		










# SPRINKLER CENTRAL



# SPRINKLER CENTRALER



# PUMPE UNIT

	1	2	3	4	5	6																																																																												
A																																																																																		
B																																																																																		
C																																																																																		
D	<p><b>Weekly Testing of System Call Fire-alarm central and inform of the testing</b></p> <ol style="list-style-type: none"> <li>1. Read the pressure on manometer (Pos.12)</li> <li>2. Open the test valve (Pos.29)</li> <li>3. The pilot pressure drops and pilot pump (Pos.23) will start.</li> <li>4. After 10 seconds pilot pump (Pos.23) will stop and the main pump (Pos.26) will start</li> <li>5. Check the alarm is indicated as on the pump control panel (Pos.3)</li> <li>6. Close the test valve (Pos.29)</li> <li>7. Observe Control Panel is operational</li> <li>8. Stop Main Pump (Pos.3) by turning S01 to "0".</li> <li>9. Read the pressure at the manometer (Pos.12). If the pressure is over the design pressure, open test valve (Pos.12) slowly until the set design pressure.</li> <li>10. Re-establishing the pump control panel by the following procedure             <ul style="list-style-type: none"> <li>• Turn main pump switch S01 to "AUTO"</li> <li>• Check pilot pump switch S04 to "AUTO"</li> </ul> </li> <li>11. Control all valves positions correct with diagram</li> </ol>																																																																																	
	<p><b>Pos. Description - State</b></p> <ol style="list-style-type: none"> <li>1. Main Pump stop</li> <li>2.1 Butterfly Valve with Limited switch - Open</li> <li>2.2 Butterfly Valve with Limited switch - Closed</li> <li>3.1 Butterfly Valve with Limited switch - Open</li> <li>3.2 Butterfly Valve with Limited switch - Closed</li> <li>12 Pilot Pump - Maintain system pressure by stop/run</li> <li>16 Manometer System pressure</li> <li>22 Drain Valve - Closed</li> </ol> <p>Activated - One or more nozzles are activated, the system pressure is reduced.</p> <p>Pressure switch Pos.9 activate the pilot pump.</p> <p>If the Pilot pump cannot maintain system pressure within 10 second, main pump is activated, and fire alarm signal is given.</p> <p>If system pressure continue to decrease below the setting value in pressure switch (Pos.9), the main pump unit will be activated by Pressure switch (Pos.9), and fire alarm signal is given. (As a back-up to the pilot alarm described in the above square)</p>																																																																																	
	<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>ITEM</th> <th>PART NUMBER</th> <th>QTY</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>35</td> <td>924016-0</td> <td>1</td> <td>Strainer DN65 3mm</td> </tr> <tr> <td>34</td> <td>3032024</td> <td>1</td> <td>Flow meter DN65</td> </tr> <tr> <td>33</td> <td>922624-0</td> <td>1</td> <td>Strainer DN65 0,5mm</td> </tr> <tr> <td>31</td> <td>921781-0</td> <td>1</td> <td>Butterfly valve DN65 Water PN16</td> </tr> <tr> <td>30</td> <td>919467-0</td> <td>4</td> <td>Diag Check Valve x DN65</td> </tr> <tr> <td>29</td> <td>921792-0</td> <td>3</td> <td>Butterfly vent DN65 LUG PN16</td> </tr> <tr> <td>26</td> <td>DR 32 4x2 30/1 116W</td> <td>1</td> <td>Pilot pump Solihass 50/80Hz</td> </tr> <tr> <td>23</td> <td>918093-0</td> <td>1</td> <td>Non return valve DN15</td> </tr> <tr> <td>22</td> <td>918093-0</td> <td>1</td> <td>Non return valve DN15</td> </tr> <tr> <td>18</td> <td>918282-0</td> <td>8</td> <td>Elbow DN15 AISI 316</td> </tr> <tr> <td>16</td> <td>911969-0</td> <td>1</td> <td>Butterfly valve DN15 FIP</td> </tr> <tr> <td>15</td> <td>924181-0</td> <td>1</td> <td>Subsolvolve with -DN25</td> </tr> <tr> <td>12</td> <td>918798-0</td> <td>1</td> <td>Manometer RPS5-0T01</td> </tr> <tr> <td>10</td> <td>918282-0</td> <td>2</td> <td>R-221 Tee DN15 AISI 316</td> </tr> <tr> <td>8</td> <td>924162-0</td> <td>2</td> <td>Pressure Switch RT116</td> </tr> <tr> <td>4</td> <td>Switchgear 500x750</td> <td>1</td> <td></td> </tr> <tr> <td>3</td> <td>30332169</td> <td>1</td> <td>Pillar for switchboard 2</td> </tr> <tr> <td>1</td> <td>30332168</td> <td>1</td> <td>Pillar for switchboard 1</td> </tr> </tbody> </table>						ITEM	PART NUMBER	QTY	DESCRIPTION	35	924016-0	1	Strainer DN65 3mm	34	3032024	1	Flow meter DN65	33	922624-0	1	Strainer DN65 0,5mm	31	921781-0	1	Butterfly valve DN65 Water PN16	30	919467-0	4	Diag Check Valve x DN65	29	921792-0	3	Butterfly vent DN65 LUG PN16	26	DR 32 4x2 30/1 116W	1	Pilot pump Solihass 50/80Hz	23	918093-0	1	Non return valve DN15	22	918093-0	1	Non return valve DN15	18	918282-0	8	Elbow DN15 AISI 316	16	911969-0	1	Butterfly valve DN15 FIP	15	924181-0	1	Subsolvolve with -DN25	12	918798-0	1	Manometer RPS5-0T01	10	918282-0	2	R-221 Tee DN15 AISI 316	8	924162-0	2	Pressure Switch RT116	4	Switchgear 500x750	1		3	30332169	1	Pillar for switchboard 2	1	30332168	1	Pillar for switchboard 1
ITEM	PART NUMBER	QTY	DESCRIPTION																																																																															
35	924016-0	1	Strainer DN65 3mm																																																																															
34	3032024	1	Flow meter DN65																																																																															
33	922624-0	1	Strainer DN65 0,5mm																																																																															
31	921781-0	1	Butterfly valve DN65 Water PN16																																																																															
30	919467-0	4	Diag Check Valve x DN65																																																																															
29	921792-0	3	Butterfly vent DN65 LUG PN16																																																																															
26	DR 32 4x2 30/1 116W	1	Pilot pump Solihass 50/80Hz																																																																															
23	918093-0	1	Non return valve DN15																																																																															
22	918093-0	1	Non return valve DN15																																																																															
18	918282-0	8	Elbow DN15 AISI 316																																																																															
16	911969-0	1	Butterfly valve DN15 FIP																																																																															
15	924181-0	1	Subsolvolve with -DN25																																																																															
12	918798-0	1	Manometer RPS5-0T01																																																																															
10	918282-0	2	R-221 Tee DN15 AISI 316																																																																															
8	924162-0	2	Pressure Switch RT116																																																																															
4	Switchgear 500x750	1																																																																																
3	30332169	1	Pillar for switchboard 2																																																																															
1	30332168	1	Pillar for switchboard 1																																																																															
	<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th colspan="2">Maintenance</th> <th>General</th> <th>Weekly</th> <th>Monthly</th> <th>Yearly</th> </tr> </thead> <tbody> <tr> <td>1.</td> <td>Pump Unit should be kept in a frost-free and fire hazard free storage</td> <td>x</td> <td></td> <td></td> <td></td> </tr> <tr> <td>2.</td> <td>Visual Check</td> <td></td> <td>x</td> <td></td> <td></td> </tr> <tr> <td>3.</td> <td>Weekly Testing of system</td> <td></td> <td>x</td> <td></td> <td></td> </tr> <tr> <td>4.</td> <td>Check All The Valve Positions are in normal state</td> <td></td> <td>x</td> <td></td> <td></td> </tr> <tr> <td>5.</td> <td>Stop and Lamp Test</td> <td></td> <td></td> <td>x</td> <td></td> </tr> <tr> <td>6.</td> <td>Pump Capability Test</td> <td></td> <td></td> <td>x</td> <td></td> </tr> <tr> <td>7.</td> <td>Pilot Pump Test</td> <td></td> <td></td> <td>x</td> <td></td> </tr> <tr> <td>8.</td> <td>Check Filter</td> <td></td> <td></td> <td>x</td> <td>x</td> </tr> <tr> <td>9.</td> <td>Check Remote Operation of Pump</td> <td></td> <td></td> <td></td> <td>x</td> </tr> <tr> <td>10.</td> <td>Check of water supply (in conjunction with the fire projection authorities)</td> <td></td> <td></td> <td></td> <td>x</td> </tr> <tr> <td>11.</td> <td>Check of alarm transfer (in conjunction with the fire projection authorities)</td> <td></td> <td></td> <td></td> <td>x</td> </tr> </tbody> </table>						Maintenance		General	Weekly	Monthly	Yearly	1.	Pump Unit should be kept in a frost-free and fire hazard free storage	x				2.	Visual Check		x			3.	Weekly Testing of system		x			4.	Check All The Valve Positions are in normal state		x			5.	Stop and Lamp Test			x		6.	Pump Capability Test			x		7.	Pilot Pump Test			x		8.	Check Filter			x	x	9.	Check Remote Operation of Pump				x	10.	Check of water supply (in conjunction with the fire projection authorities)				x	11.	Check of alarm transfer (in conjunction with the fire projection authorities)				x				
Maintenance		General	Weekly	Monthly	Yearly																																																																													
1.	Pump Unit should be kept in a frost-free and fire hazard free storage	x																																																																																
2.	Visual Check		x																																																																															
3.	Weekly Testing of system		x																																																																															
4.	Check All The Valve Positions are in normal state		x																																																																															
5.	Stop and Lamp Test			x																																																																														
6.	Pump Capability Test			x																																																																														
7.	Pilot Pump Test			x																																																																														
8.	Check Filter			x	x																																																																													
9.	Check Remote Operation of Pump				x																																																																													
10.	Check of water supply (in conjunction with the fire projection authorities)				x																																																																													
11.	Check of alarm transfer (in conjunction with the fire projection authorities)				x																																																																													
	<table border="1" style="width:100%; border-collapse: collapse;"> <tr> <td colspan="2">  </td> <td colspan="2">  </td> </tr> <tr> <td colspan="2">                 PUMPUINT             </td> <td colspan="2">                 DRAWINGNO             </td> </tr> <tr> <td colspan="2">                 WATERMIST             </td> <td colspan="2">                 PUMPE             </td> </tr> </table>										PUMPUINT		DRAWINGNO		WATERMIST		PUMPE																																																																	
																																																																																		
PUMPUINT		DRAWINGNO																																																																																
WATERMIST		PUMPE																																																																																

# UDFØRTE PROJEKTER CAMPUS VARDE






# MIKADO HOUSE, KØBENHAVN





# VAT 83, GLADSAXE



# KRÆFTENS BEKÆMPELSE, ÅRHUS



# INSPEKTION / GODKENDELSE



Inspektionsrapport

## Vandtågeanlæg

Bygning/område:

Campus

Anlægstype:

Automatisk vandtågeanlæg

Risikoklasse:

OH 2

Vandtæthed, mm/min.:

1,6 mm/min

Krav til vandforsyning:

404 l/min. 6,5 bar

Første inspektion

**Campus**  
**Frisvadvej 72**  
**6800 Varde**

Sag: IA06035

Inspektion udført: 2011-03-31  
Rapport udstedt: 2011-05-10  
Inspektør: Kurt Søballe Andersen

Inspektionsafdelingen

Aftapningsprøve fra 1. inspektion

Vandmængde l/min.	Venstre lukket				Højre lukket				Begge åbne			
	UP	P1	P2	P3	UP	P1	P2	P3	UP	P1	P2	P3
2011-03-31												
0	3,1	11,0			3,1	11,5			3,2	11,0		
250	2,5	10,8			2,9	10,8			3,2	10,9		
405	1,1	9,7			2,8	10,5			2,9	10,5		
500	0,7	8,0			2,7	9,0			2,8	9,8		

### Inspektionsresultat

**GODKENDT anmærkningsfrit.**

**DTEK®**

Dansk Teknikentreprise A/S

# FORDELE MED XFLOW SYSTEM

- mindre vand – mindre energi - miljø venlig
- quick respons
- hurtig kontrol med branden
- mindre vandskade ved fejl aktivering
- diskret rør installation med tyndvæggede presrør
- små rør, større spacing - mere plads til de andre installationsfag
- mindre reservoir
- mindre pumper - både økonomisk og pladsmæssigt
- nem installation
- lav vedligeholdelses omkostninger

END

**DTEK®**

Dansk Teknikentreprise A/S