



The Building Layout

The Design

System Layout

Water and Power Supply


The Quality Process



ABENA

Building Layout

- Office building
- Two stories and parterre level
- Car park in parterre





ABENA

Building Layout

- Total of 6,850 m²
- Office 6,300 m²
- Car park 550 m²





hazard classification

- Hazard classification against DBI CEA 4001 "Sprinkler systems Design, installation and maintenance":
 - Office levels Ordinary Hazard group 1 (OH1)
 - Car park Ordinary Hazard group 2 (OH2)







fire test

- CEN/TS 14972 for Office fire test
- Office levels Ordinary Hazard group 1 (OH1)







fire test

- Sprinkler test
- Spacing $3.5m \times 3.5m$

- Water mist test
- Spacing $5.5 \text{m} \times 5.5 \text{ m}$







installation

• Nozzle head with 6 micro nozzles

• Press fitting for easy assembly of the pipes in the installation







installation


• Motor valve as section valve





pump unit

- Two high pressure pumps operating together to generate the required pressure
- One jockey pump for containing system pressure








water and power supply

- One electric generator
- One diesel generator
- Water supply directly from two stainless steel tanks
 - Ensures that the system can operate independent of public water supply
 - Water capacity for 30 minutes (Dispensation)





control system

- Two individually switch boards
 - One for electric
 - One for diesel



service and maintenance

• Regularly test

- Start-up of pump unit once per week
- Flow test



Acknowledgements

- Steen Aakjær, Zeni arkitekter a/s
- Preben A. Christensen, Danfoss Semco A/S Fire Protection
- Jens T. Jepsen, Danfoss Semco A/S Fire Protection
- Bo Rasmussen, Danfoss Semco A/S Fire Protection
- Xue Zhang, Danfoss Semco A/S Fire Protection
- Carsten Windt, Danfoss Semco A/S Fire Protection
- See more about Danfoss Semco A/S Fire Protection's SEM-SAFE® system on

www.danfoss-semco.com